

PROFLEX_® 7236

Features


- ExoCrylic™
- Drop-in or three-wall alcove
- Molded lumbar support and armrests for comfort
- Optional K-1491 removable bath pillow
- Optional K-1283 removable apron
- Optional K-1601 removable footstop
- 72" (1829 mm) x 36" (914 mm) x 20-1/8" (511 mm)

Codes/Standards Applicable

Specified model meets or exceeds the following:

CSA B45.5/IAPMO Z124





Colors/Finishes

- 0: White
- Other: Refer to Price Book for additional colors/finishes

Accessories

- 0: White
- CP: Polished Chrome
- PB: Vibrant_® Polished Brass
- Other: Refer to Price Book for additional colors/finishes

Specified Model

Model	Description	Colors/F	Colors/Finishes		
K-1159	Bath, drop-in (shown)	□ 0	☐ Other		
K-1159-L	Bath, tile flange, left drain	□ 0	□ Other		
K-1159-R	Bath, tile flange, right drain	□ 0	☐ Other		
Recommended Accessories					

K-11677	Swiftflo™ adjustable trip lever bath drain	□ CP	□ PB		
Optional Accessories					
K-1283	Removable apron	□ 0	☐ Other		
K-1491	Removable bath pillow	□ 0	☐ Other		
K-1601	Removable footstop	□ 0	☐ Other		

Product Specification

The ExoCrylic bath shall be 72" (1829 mm) in length, 36" (914 mm) in width, and 20-1/8" (511 mm) in height. Bath shall be for drop-in [K-1159] or three-wall alcove installation [K-1159-L/-R]. Bath shall feature molded lumbar support and armrests for comfort. Bath shall feature optional K-1283 removable apron, K-1491 removable bath pillow, and K-1601 removable footstop. Bath shall be Kohler Model K-1159-____ or K-1159-_

PROFLEX_® 7236

Technical Information

Fixture*:				
Bathing well:				
Basin area, bottom	55" (1397 mm) x 21" (533 mm)			
Basin area, top	65" (1651 mm) x 26" (660 mm)			
To overflow:				
Water depth	15" (381 mm)			
Capacity	72 gal (272.5 L)			
Weight	52 lbs (23.6 kg)			
Drop-in cutout	70-1/2" (1791 mm) x			
	34-1/2" (876 mm)			
* Approximate measurements for comparison only.				

Installation Notes

Install this product according to the installation guide.

Floor support under bath must provide for a minimum of 38 lbs/square foot (184 kg/square meter) loading.

The apron must be installed before the finished floor and wall materials are installed.

